COMBAT RATION NETWORK FOR TECHNOLOGY IMPLEMENTATION

Multivac Installation

Final Technical Report STP 1014

Results and Accomplishments (March 1999)

Report No: FTR 105

CDRL Sequence: A004

February, 2000

CORANET CONTRACT NO. SPO103-96-D-0016

Sponsored by: DEFENSE LOGISTICS AGENCY 8725 John J. Kingman Rd. Fort Belvoir, VA 22060-6221

Contractor:

Rutgers, The State University of New Jersey THE CENTER FOR ADVANCED FOOD TECHNOLOGY* Cook College N.J. Agricultural Experiment Station

New Brunswick, New Jersey 08903

Principal Investigator: Neal Litman

Dr. John F. Coburn Program Director

TEL: 732-445-6130 FAX: 732-445-6145

20001017 023

DISTRIBUTION STATEMENT A

Approved for Public Release Distribution Unlimited

Read and Write

	SCIENTIFIC	AND TECHNICAL	L INFORMA	TION SYSTEM
. Acc. Number 08000793	1A. Act. Code A Add A		tus 4. Perf. Me C Contrac	
Performance Ty	2000/10/06		7	End Date 999/07/31 Continuous End
10. Sec. Class. U Unclassified	18. Distribution Code A Distribution Unlimite	19. Distribution Read PB Public Release	son	
20. Title STP 1014, MUL	TIVAC HORIZONTAL FOI	RM, FILL, AND SEAL I	MACHINE INST	ALLATION
	22. Linking Accession Nu	mber (Select Up to	23. Local Co	ntrol Number 24. Search Data
	Two)		98005, STP	1014
	25. Subject Categor	ies		
	Code		Description Manufactu	n uring and Industrial Engineering and
	1308		Control of	Production Systems
	26.1 Mission Area	And common the common was served, and it is not a served definition of the common and co	A VAN AAA TARRARA	
	Code 5.1		Description Logistics	1
	3.1			
	26.2 Function Code			
	Code		Description	
	7.2		Manutact	uring Technology
AA-WARRANTANANAN MAAA -WAA	26.3 Technology Co	ode	make an and at \$ 1.5 to \$ 10.5 km. And the second at \$ 1.5 to \$10.5 km.	en partir de commence de la companya del companya del companya de la companya de
	Code		Descriptio	
	4.2.2		4.2.2 Man	ufacturing Cell Control Technology
27. Resp. Org 27.2 Respons	g. Source 27.1 432549 27.1 sible Organization Comp	Responsible Organiz	zation Name	un deliminated believe (in the company of the compa
27.4 Responsi				
Last Name		First Name		MI
27.5 Resp. Ir	ndiv. Off. Sys.	27.6 Resp	. Indiv. Phone	27.7 Resp. Indiv. DSN No.

28. Perf. Org. Source 200 (200) 28.1 Performing Organization Name

28.2 Performing Organization Component Name

28.4 Performing Individual

Last Name

First Name

MΙ

28.5 Perf. Indiv. Off. Sys.

28.6 Perf. Indiv. Phone

28.7 Perf. Indiv. DSN No.

28.8 Associate Investigator Names (Last, First, MI)

LITMAN

NEAL

35. Keyword Text

RATIONS

THERMOSTABILIZED

POUCHES

PREFORMED

HORIZONTAL

QUALITY

MACHINE VISION

ROBOTICS

DUAL USE

FLEXIBILITY

INTEGRATION

SHOP FLOOR

36.1 Objective

THERE WAS A NEED TO HAVE A MODERN HORIZONTAL FORM, FILL, SEAL MACHINE FOR COMBAT RATION POUCHES IN HOUSE AT THE DEMONSTRATION SITE, OF THE TYPE BEING USED IN INDUSTRY, TO MAKE DEMONSTRATIONS MORE MEANINGFUL. AT THE SAME TIME, THERE WAS AN OPPORTUNITY TO DOCUMENT THE STEPS INVOLVED IN ACQUIRING, MOVING, INSTALLING AND INTEGRATING THE EQUIPMENT INTO THE PRODUCT FLOWOF ANY MANUFACTURING ESTABLISHMENT. SUCH DOCUMENTATION WOULD BE A GUIDE FOR FUTURE ACTIVITIES.

37.1 Approach

SINCE THE DEMO SITE HAD PREVIOUS EXPERIENCE IN MOVING, INSTALLING AND INTEGRATING HFFS EQUIPMENT INTO THE DEMO SITE, AND SINCE THEY NEEDED A NEW AND MODERN MACHINE OF THE SAME TYPE AS USED BY RATION PRODUCERS, THEY WERE ASKED TO DOCUMENT THE PROCESS.

38.1 Progress

THE EQUIPMENT WAS MOVED IN, INSTALLED, AND SET UP FOR RUNNING. A VARIETY OF POUCHES WERE PRODUCED AS PART OF OTHER PROJECTS. SINCE THE MULTIVAC HFFS HAS EXCELLENT CONTROL FEATURES AND PROVIDES REPEATABILITY, THE PRODUCTS CAN BE USED AS TEST ARTICLES IN SPECIFIC EXPERIMENTAL EFFORTS. THE FINAL REPORT IS NEARING COMPLETION.

30. Primary PE No.

31. 1st Contrib. PE No.

32. 2nd Contrib PE No.

0708011S

30A. Primary Proj. No.

31A. 1st Contrib. Proj. No.

32A. 2nd Contrib. Proj. No.

98005

30B. Primary Task No.

31B. 1st Contrib. Task No.

32B. 2nd Contrib. Task No.

STP 1014

	ry Funding (Data	31. 1st Co	nt. Fundin	g Data	32. 2nd Cor	nt. Funding D)ata	33. Contract	
Fiscal Year	Dollars	Work Year	Fiscal Year	Dollars	Work Year	Fiscal Year	Dollars	Work Year	Rollup Indicator	
C1	C2	C3	C1	C2	C3	C1	C2	СЗ	C	
1998	9496	1								
D1	D2	D3	D1	D2	D3	D1	D2	D3	D	
E1	E2	E3	E1	E2	E3	E1	E2	E 3	E	
F1	F2	F3	.l F1	F2	F3	F1	F2	F3	F	
G1	G2	G3	G1	G2	G3	G1	G2	G3	G G	
						.:[
39A. Pro	duct Set No.	39. Co	1A Prod. Ti de	tle Class	39.2A Pro	oduct Title				
20 2 P-	oduct ID/Rej		classified		39 14 Pro	oduct AD No	39 54	Product Inc	dicator	
AND THE PROPERTY OF A PROPERTY OF A PARTY.	A ANY STREAMSTON	AMERICAN STREET, STREE	ENGLISHMENT TO THE	Commence to a 1 a 4 bulle			TARREST TO ST.	remain in the second sec	Photogramma and an analysis of the second se	
39B. Pro	duct Set No.	. 1	.1B Prod. Ti	tle Class	39.2B Pro	oduct Title	A CONTRACT OF THE PROPERTY OF	THE PARTY OF THE P		
39B. Pro	duct Set No.	Co		tle Class	39.2B Pro	oduct Title	A Warnessmannschaft von 1981		SANDARA PRANTISA V	
	duct Set No.	Co Un	de	tle Class		oduct Title	39.5B	Product Inc	dicator	
39.3B Pr	PRISA ACCORDINATION CONTRACTOR STATES AND ACCORDINATION CONTRACTOR AC	Co Un port No 39	de		39.4B Pro	A section of the sect	[39.5B	Product Inc	dicator	
39.3B Pr	oduct ID/Re	Co Un port No 39	classified		39.4B Pro	oduct AD No				
39.3B Pr	oduct ID/Re	Don't No 39 Co	classified .1C Prod. T		39.4B Pro	oduct AD No		Product In		
39.3B Pr	oduct ID/Re	Don't No 39 Co	classified .1C Prod. T		39.4B Pro	oduct AD No				
39.3B Pro 39C. Pro 39.3C Pr	oduct ID/Re	Dort No 39 Co Un port No 39 Co Un port No	classified .1C Prod. T	itle Class	39.4B Pro	oduct AD No				
39.3B Pro 39C. Pro 39.3C Pr	oduct ID/Re	Dort No 39 Co Un port No 39 Co Un port No	.1C Prod. Tode classified	itle Class	39.4B Pro 39.2C Pro 39.4C Pro	oduct AD No oduct Title oduct Title	39.50	Product Inc	dicator	
39.3B Pro 39C. Pro 39.3C Pro	oduct ID/Re	Co Un port No 39 Co Un port No	.1C Prod. Tode	itle Class	39.4B Pro 39.2C Pro 39.4C Pro	oduct AD No	39.50		dicator	
39.3B Pro 39C. Pro 39.3C Pro	oduct ID/Re	Co Un port No 39 Co Un port No	.1C Prod. Tode	itle Class	39.4B Pro 39.2C Pro 39.4C Pro	oduct AD No oduct Title oduct Title	39.50	Product Inc	dicator	
39.3B Pro 39C. Pro 39.3C Pro 39D. Pro	oduct ID/Re	port No 39 Co Un port No 29 Co Un port No 29 29 29 29 20 20 20 20 20 20 20 20 20 20 20 20 20	.1C Prod. Tode	itle Class	39.4B Pro 39.2C Pro 39.4C Pro 39.2D Pro	oduct AD No oduct Title oduct Title	39.50	Product Inc	dicator	
39.3B Pro 39C. Pro 39.3C Pro 39D. Pro 39.3D Pro	oduct ID/Re	Don't No 39 Co Un	.1C Prod. Tode .1D Prod. Tode .1E Prod. T	itle Class	39.4B Pro 39.2C Pro 39.4C Pro 39.4D Pro 39.4D Pro 39.2E Pro	oduct AD No oduct Title oduct Title oduct AD No	39.5C	Product Inc	dicator dicator	

34. Contract/Grant/Trans. No. 34.2 Contract Expiration Date SDO 108-96-4 -00/6 7000 07 26	34.1 Contract Effective Date 34.3 Contract Face Value (1986) 14 94,600,	34.4 Contract Cum. to Date
40. Dom. Tech Trans.	HI High potential for civilian application	The party of the second of the
41. Study Category	5 Science, Technology, Systems and Equipme	ent
42. Spec. Study Sub	CA Capability analysis	
44. Prim. Proj. Serial No		many and a second of the secon
45. Int. Sources Con.	Y	
46. Processing Date	!	
47. Receipt Date	Annual Carlos and Carlos and Carlos	taling the state of
49. Thrust Indicator Technology for Affordability		and the second s

Status Code

Russell Eggers

Focal Point

Requires Focal Point Attention

Author

Mark Glover

REPORT DOCUMENTATION PAGE

Form Approved
OMB No. 3704-0188

La scription of duction in the action of internations of maked to service and other response, including the time for reviewing instructions, searching data sources, pathenning of internation of the action of the

	PE AND DATES 98 - Jan. 0	COVERED	
4. TITLE AND SUBTITLE		DING NUMBERS	_
Multivac Installation 3. AuTHOR(S)	PE	20103-96-D-0016 E-7811s E-88003 9,000 5	
Neal Litman	Allender or the caleboar	7 300 9	
7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS.ES)		ORMING ORGANIZATION	
Rutgers, The State University of New Jersey The Center for Advanced Food Technology Cook College, NJ Agricultural Experiment Station New Brunswick, NJ 08903	REPU	FTR-105	
9. SPONSORING (MONITORING AGENCY MAME(S) AND AUDRESS(ES)		NSORING/MONITORING NCY REPORT NUMBER	
Defense Logistics Agency 8725 John J. Kingman Road Ft. Belvoir, VA 22060-6221			
11. SUPPLEMENTARY NOTES			
12a. DISTRIBUTION, AVAILABILITY STATEMENT	12b. DIS	TRIBUTION CODE	
		÷	
13. ABSTRACT Maximum 200 words)			
This report covers the activities of CORANET STP #1014, Multivac project, two GFE Multivac Horizontal Form-Fill-Seal packaging line the equipment with current readiness requirements. Logistic and tech large machines were fully documented. Installation, Startup and Acc were reported. including plant requirements and packaging materials	es were re-deple hnical issues we ceptance of the	loyed to align	
14. SUBJECT TERMS		15. NUMBER OF PAGES	
		16. PRICE CODE	
17. SECURITY CLASSIFICATION 18. SECURITY CLASSIFICATION 19. SECURITY CL OF REPORT OF THIS PAGE OF ABSTRAC		20. LIMITATION OF ABSTRAC	T

Unclassified

Unclassified

UL

Unclassified

Table of Contents

1.0	Introduction	
2.0	Background	-
3.0	Activities	3
3.1	Relocation of Land O'Frost Machine (Task 4.2.1)	3
3.2	Relocation of Sterling Machine (Task 4.2.2)	4
3.3	Installation at FMT Facility (Task 4.2.3)	4
3.4	Acceptance Run (Task 4.2.4)	-
3.5	Engineering (Task 4.2.5)	-
4.0	Technical Discussion	4
4.1	Equipment Shipping and Rigging	4
4.2	Utilities	(
4.3	Equipment Documentation and Training	(
4.4	Packaging Materials	(
4.5	Tooling	(
4.6	Data Acquisition System	(
4.7	Y2K Compliance	
4.8	Multivac Modifications	,
4.9	Videojet Printer	,
4.10	Acceptance Test	,
4.11	Filling System Integration	-
5.0	Recommendations and Conclusion	-
6.0	Appendix	
6.1	Project Management Plan and Schedule	
6.2	Equipment Installation Manual	
6.3	Equipment Transportation Manual	
6.4	Equipment Set Up - Rutgers U. FMTF	
6.5	Equipment Data Sheets; Multivac R530 Set Up, Program Log, QC Record	
6.6	Installation Photos	
6.7	Lawson-Marden Singen - Flexalcon Technical Information	
6.8	Multivac R530/#645 Machine Card and Tooling	
6.9	Multivac R530/#667 Machine Card and Tooling	
6.10	Multivac Y2K Documentation	
6.11	Multivac R530/#667 Shipping List	
6.12	Rutgers U. FMTF / CORANET Demo Site Plant Layout Drawing	
6.13	Organization Chart for Multivac Redeployment	

1.0 Introduction

The CORANET Demonstration Site at Rutgers University Food Manufacturing Technology Facility is equipped with commercial packaging lines (a Tiromat HFFS for MREs and a Raque Heat Sealer for polymeric trays) along with cooking capability and sufficient retort capacity to be able to demonstrate full-scale production of Combat Rations. In the case of MRE production, MRE production at producer sites is currently based on recently acquired Multivac HFFS machines rather than the Tiromat which CRAMTD purchased in 1990. In particular, the availability of a Multivac machine at the Demonstration Site will enhance the technology transfer of Machine Vision Inspection STP #1007 which is to take place at the Demonstration Site and which earlier would have been targeted at Tiromat equipment. The Delivery Order for STP #1014 was received on July 14, 1998.

2.0 Background

Multivac R530 packaging lines were purchase by the military to assure MRE readiness by adding to the surge capacity needed for war-time. As such, six lines were deployed at contract producer facilities. These machines are capable of producing non-military products, and therefore provide a dual use in peace-time as well. The machines are quite large and to relocate one to another manufacturing site requires planning for the necessary technical and logistic support. The military, in general, does not possess this in-house capability for undertaking a redeployment. Rutgers University has been involved with the rations manufacturing program and was directly involved with the development of HFFS for the MRE. Rutgers was therefore a qualified technical resource for managing the relocation of Multivac equipment.

The Demonstration Site for the CORANET Program requested a Multivac HFFS machine for high speed/high volume production during development and production runs, so that processes can be developed and demonstrated to the CORANET Partners using equipment with which they are familiar. The existing Government owned Tiromat equipment that is currently being used in the Demonstration Site can operated for other packaging projects for which its production capabilities can be demonstrated, such as thermoforming. This justification was the basis for relocation of one Multivac HFFS to Rutgers U. FMTF and the CORANET Demonstration Site.

3.0 Activities

3.1 Relocation of Land O'Frost Machine (Task 4.2.1)

Contracting arrangements were initiated with Multivac. Inc. for the relocation of the machine R530/#667 located at the Land OFrost plant in Lansing, IL. The work scope included; a service technician on-site, shipping pallets (original pallets were not retained), rigging and transportation to San Antonio, TX. The cost quotation of \$27,680 and revised quotation of \$24,690 was deemed excessive and well over the budget. PM Russell Eggers concurred with Rutgers recommendation of delaying the relocation to explore other options. A Chicago based rigger, MSI Inc., was ultimately contracted for rigging and transportation, while Multivac insisted that Rutgers cover the expense of pallets that had already been fabricated and would provide a service technician to assist. The dates of the equipment relocation changed from September 28-29 to October 1-2, 1998, which were acceptable to Land OFrost.

Utility connections were removed from the machine prior to the arrival of the Multivac technician. The following is a list of the steps taken by the technician:

- 1. Remove discharge conveyor and bottom web mandrel assembly.
- 2. Unbolt top forming station from machine frame, disconnect electrical wiring and pneumatic hoses.

- 3. Lift top forming station off machine, rigging straps paced through frame (top guard must be removed).
- 4. Disconnect vacuum hose and electrical wiring to roots blower and at junction box.
- 5. Loosen chain tension at forming station, break chain at motor drive and remove chain.
- 6. Remove bolts and brackets where machine halves join.
- 7. Attach clamps and shipping bars to legs.
- 8. Secure and cover loose wires and hoses, secure film unwind dancer arms.
- 9. Replace side covers, guards and support rails.

Shipping pallets delivered to Land OFrost by Multivac's shipping contractor were found to be inadequately constructed despite having been given construction drawings. Multivac was unable to get the pallets fixed quickly, so the pallets were discarded. This caused a serious problem because Land OFrost demanded the machine be removed over the weekend and would not allow any further rigging in the production area during weekdays. The rigging contractor agreed to build new pallets and complete the job on the weekend at premium labor rates. The additional rigger cost was offset by the refusal of the Multivac pallets. Detailed documentation for the equipment is contained the Machine Card found in Appendix 6.9.

3.2 Relocation of Sterling Machine (Task 4.2.2)

Multivac machine R530/#645 was held in storage at Sterling Foods in San Antonio, Texas on their original shipping pallets and ready for transportation. Multivac was hired to handle the transportation of the machine to Piscataway, NJ via their usual shipping service, Rotra Inc. Sterling Foods agreed to load the equipment onto a semi-trailer. The machinery was picked up at Sterling Foods on July 24, 1998 and delivered to Rutgers U. FMTF on August 5, 1998 after several truck delays.

3.3 Installation at FMT Facility (Task 4.2.3)

An order was placed for Lawson Mardon film in July, 1998. Since our order was for less than a minimum quantity, our order was held up until an MRE film order was placed by a retorter. The film was delivered on November 20, 1998. The film being the long lead item controlled the schedule for machine start up.

Riggers unloaded machine pieces August 5, 1998 and moved them to the production area. The two major pieces were lifted by forklift off wooden shipping pallets and connected together into their final position, location shown in Appendix 6.12. Steel angle beams were removed from the machine legs and with the shipping pallets placed in the warehouse for storage.

Electrical work was accomplished in September 1998. Electric conduit and wiring was run from the ceiling down to the Multivac and to the Busch vacuum pump. Cost for electrical work was \$4210.

Plumbing work was accomplished by a contractor from September to October 1998. The primary compressed air supply pipe above the ceiling had to be extended approximately 30 feet. The piping drop was located at the side of the main control panel, near the printer nozzle support. The pipe was fitted with a shut off valve and teed at the bottom. A two inch pipe was selected to provide ample volume of air to the Multivac without the need for a surge tank, as was required for the Tiromat installation. A short length of hose was used to connect the tee to the main control cabinet, the opposite side of the tee was connected to a length of one inch pipe fixed to the legs of the Multivac and led to the forming system control cabinet. Several utility connections were placed along the pipe run. A cold water supply was run adjacent to the air line with a shut off valve. The water was discharged to a nearby floor drain through half inch tubing. A three inch PVC pipe was used for connecting the vacuum pump to the Multivac. The vacuum pump was located approximately ten feet from the Multivac to minimize pipe length, a total of 30 feet of pipe was used. Total cost for plumbing was \$4325.

A Multivac service technician completed the machine installation from December 7 to December 18, 1998. The cost for a new machine installation was covered under the purchase of the machine and therefore not charged to Rutgers or this Short Term Project. For informational purposes, the work totaled 54 hours at a cost of \$5940 plus travel time and expenses of \$3827. The tasks performed:

- 1. Confirm proper utility connections.
- 2. Connect two machine sections; frame, wiring and pneumatics.
- 3. Install Top Web Forming Unit, Roots Blower Vacuum Booster, Vibrator, Film Mandrels and Videojet printer
- 4. Machine leveling
- 5. Install film transport chain
- 6. Ran machine, making adjustments
- 7. Basic operator and safety training

3.4 Acceptance Run (Task 4.2.4)

The Acceptance Test for Multivac #645 was held at Rutgers U. FMTF on January 6, 1999. The test objectives were verification of machine capability and performance, specifically meeting the packaging requirements of MIL-PRF-44073. The tests were conducted with Grilled Chicken Breast. Pouches were produced, inspected then retorted and evaluated by the QC technician. A random sampling of pouches were tested with the result that no defects were found and all MRE requirements were met. A batch of water filled pouches were also run to subject the machine to a lengthy run. The machine performed well, the only noted problem was the machine cycle rate being only 6.7 per minute, when 15 cycles per minute was the rated design. The low machine speed can be attributed to the operational parameters determined by Multivac. It is believed that these parameters were optimized for seals. Work would be required to significantly improve the machine cycle rate.

3.5 Engineering (Task 4.2.5)

Equipment information was gathered from Multivac to plan for relocation and machine installation. Multivac supplied the following documents;

- 1. Machine Card (Appendix 6.8)
- 2. Machine drawings (Lageplan)
- 3. Manual for Transport, Storage, Installation. Start-up/Shut-down (Appendices 6.2 and 6.3)
- 4. Shipping Descriptions and Weights

Contracts with riggers, electricians, plumbers and freight service were proceeded by initial vendor consultations and job quotations based on the equipment and facility requirements.

In the course of machine testing and Acceptance, Quality Control performed tests on pouches to verify MRE specification were satisfied.

Preliminary engineering of filling equipment and retort loading equipment was investigated with filling equipment vendors to determine the cost of retrofitting existing pilot plant filling systems: Solbern Net Weight filler. Oden Pump filler, and Adept robot.

4.0 Technical Discussion

4.1 Equipment Shipping and Rigging

The Multivac equipment is shipped as two large pieces along with additional parts, a description with weights are shown in Appendix 6.11. All pieces are shipped on wooden pallets to facilitate handling and protection. The entire machine and accessories ship in one large box

trailer, 52 feet long by 102 inches wide. As with most machinery containing electronic components, the Multivac should be transported in a trailer equipped with an air-ride suspension.

The Multivac is originally shipped from the factory in Germany on pallets and secured with shipping rails. The rails and leg clamps are to be warehoused for possible equipment relocation. The rails are steel angles with notches cut for each leg. The Multivac is lifted by the rails only, otherwise the machine frame can be damaged. The pallets are constructed from 6 x 6 inch lumber, running the length of each machine section with cross pieces nailed as decking.

4.2 Utilities

The following are utility requirements for the machine: Electrical - 220 volt, 3 phase, 60 cycle, 80 amps: Compressed air - 80 c.f.m. at 100 psi: Water - 50 gallons/hour, 50-80°F. These hookups are accomplished by local electrical and plumbing tradesmen. Depending on the availability of utilities, this will take 2-4 days of installation time.

4.3 Equipment Documentation and Training

Multivac supplies a complete set of documentation for the machine; Instruction Manual. Information for Service Technicians. Spare Parts Catalog, Description of the "Peer To Peer" Data Interface. These manuals indicate machine serial number, thus are specific and must be kept with each machine. Videojet supplies the following manuals as well; Owners Manual, Service Manual and Printer Reference Guide.

The service technician performing machine installation provides an introductory training session, covering the operator display panel, basic machine operation and machine safety features. Multivac holds a one week training course for key plant operators at its Kansas City facility. This course is included at no charge with the purchase of each machine.

4.4 Packaging Materials

Lawson-Mardon Singen is the supplier of MRE packaging film for the Multivac HFFS machine. The US agent is Winter-Wolff International, phone (516) 997-3300, Attn: Mr. Daniel Weil. Delivery lead times for MRE films are 2-4 months from order. Technical information and specification for the Lawson-Mardon Singen material can be found in Appendix 6.7. The formable bottom web consists of four plies: inner layer of polypropylene sealant, nylon, aluminum foil and oriented polypropylene. The top web consists of three layers; polypropylene sealant, aluminum foil and polyester. No other suppliers are approved at this time.

4.5 Tooling

The current tooling supplied with the machine is designed for producing MRE pouches with foil laminate. Both Multivac machines #645 and #667 have tooling upgrades installed. The tooling depth (package thickness) can be adjusted from 25mm to 49mm, but package depth is controlled by a combination of parameters: plug depth, forming mold depth, forming assist air pressure and forming duration. The maximum pouch volume is limited by the forming characteristic of the film. The machine has a top web forming unit installed, however there is no material presently available for this purpose and is unlikely the feature will be used for the production of MREs. Furthermore, the top web forming system reduces the Loading Area of the Multivac. The machine was delivered with an Air Assist Forming System that when installed can thermoform thin plastic materials into pouches.

To produce a semi-rigid package (such as a tray), new forming and sealing dies, and cutting tools will be required. An estimate of the cost to add new tooling is \$120,000; \$60,000 for new plug assist with pre-heat dies and \$60.00 for sealing dies and cutting tools.

The sealing tooling has been fabricated with gas ports to allow Modified Atmosphere Packaging capability. Valves and sensors are mounted, but not connected. Some additional hardware installation will be required as well as a revised control program which is supplied in a replaceable EPROM chip. This work accomplished by a Multivac Service Technician will cost approximately \$5,000.

4.6 Data Acquisition System

The communication interface makes it possible to create a data communication between the packaging machine and a personal computer (Gateway2000 P120). The interface hardware is a V24/RS232 serial port on the Multivac logic controller to an Allen-Bradley Communication Adapter running DH485 protocol. The adapter connects to the PC serial port. The PC can read and write data blocks to the Multivac controller program memory. The data available includes: machine status, diagnostics and fault messages, machine settings and readings, contents of program memory, machine terminal display and status of machine control inputs and outputs.

The PC as provided does not have application software installed. To use this capability, the plant must purchase a separate program or develop a custom in-house program. Multivac has been unresponsive regarding support of this product other than information provided in the manual "Description of the Peer To Peer Data Interface." The Data Acquisition System at the Demonstration Site is therefore unusable at this time.

4.7 Y2K Compliance

Multivac, Inc. has certified that R530 packaging machines do not use date based functions and therefore are unaffected by the change to the year 2000. They have made statements to further certify their business operation and suppliers, see Appendix 6.10. Peripheral equipment such as the Videojet printer are also compliant.

4.8 Multivac Modifications

An upgrade kit was installed in Multivac #645 when the machine was in Kansas City that included the latest tooling modifications. During start up of the machine at Rutgers U. FMTF, the service technician discovered a number of defectively manufactured solenoid valves. Multivac replaced these valves at no charge under warranty.

4.9 Videojet Printer

Installation and start up of the Videojet Ink Jet printer was included with the purchase of new equipment at no additional cost. A Videojet service technician was dispatched as a new printer requires a significant time to assemble, load ink and calibrate. The printer has two print heads that traverse the top web during Multivac cycle dwell. The label is repeated for each of the four package lanes. To assure MRE pouches are labeled, the Multivac can be set to stop running should the printer detect a print problem. A Videojet manual was supplied with the unit.

4.10 Acceptance Test

An Acceptance Test consisted of producing approximately 200 pouches of grilled chicken breast. Twenty samples were selected randomly following retorting. Each pouch was examined for defects in accordance with Table II, 10 pouches were tested for residual gas volume and 10 pouches were tested for internal pressure. Pouches passed all inspections. In addition, residual gas averaged 8cc with a standard deviation of 0.9cc. Pouch volume prior to filling averaged 10.4 ounces (295cc).

4.11 Filling System Integration

Budget quotes were received from Solbern of \$75,000 for a Dumper mechanism compatible with the existing tumble filler and from Oden Corporation of \$51,139 for expanding our existing filler to 8 pouches. Oden also quoted on a new filler for the Multivac of \$130,978. The implementation of the Adept PackOne robot filling system would require a second robot to meet the requirements for maximum line speed of 120 packages per minute. Cost for the robot filling system retrofit is \$175,000. The inspection conveyor currently located at the Tiromat discharge can be relocated to the Multivac with room for the retort crate loaders.

5.0 Recommendations and Conclusion

The Multivac HFFS packaging line was purchased by the military with "war-stopper" funds justified by the mobilization needs for MRE rations. The machine serves this purpose very well. It produces a quality MRE package with additional benefits. The Multivac has superior headspace control and convenient horizontal pouch loading for placeable food items. This project has demonstrated the ability to redeploy the Multivac to another processing plant within weeks. This report covers the logistics issues for relocation and documents the most cost effective and appropriate procedures for accomplishing a redeployment.

The recommended team organization for accomplishing a relocation is shown in Appendix 6.13. This organization gives the Project Manager control of coordination, schedule and costs. This arrangement produced satisfactory results within the budget and schedule of this STP.

The use military transportation services DSC Richmond - JHA were also considered but not selected due to a very high cost quotation.

Appendix 6.1

Figure 1 - CORANET Short Term Project #1014 Multivac HFFS Installation At Demonstration Site Management Plan and Schedule

				19	98			1999
Task Name	WBS	Jul	Aug	Sep	Oct	Nov	Dec	Jan
Relocate Land O'Frost Machine	4.2.1							
Relocate Sterling Machine	4.2.2							
Install at FMT Facility	4.2.3							
Acceptance Run	4.2.4							
Engineering	4.2.5							
Final Report	4.2.6							\Q


Appendix 6.2

Equipment Installation Manual

R 530

Contents

- O Safety
- O Installation
- O Electrical connections
- O Compressed air connections
- O Cooling water connections
- Vacuum connections
- Gas connections
- O Final checks
- O Layout plan, connection diagram



Safety



Danger that the machine may topple over!
Danger of injury!

- When assembling machine parts, use suitable lifting equipment or obtain the assistance of another person
- Follow the transport instructions
- Electrical connections should only be made by trained electricians and the relevant regulations must be observed
- When fitting the dies and additional equipment follow the safety instructions in the description


Installation

We recommend that you request the help of a Multivac service technician when installing/starting up a machine

- Undo all attachment screws (1)
- Remove the transverse (2) and longitudinal (3) wooden supports
- Use a fork-lift truck to lift the machine slowly by the L-bars (7) until the crossbeam (4) is accessible


Unpacking, preparation

- Remove the outer packaging (film, board. wooden case)
- Remove all transport safety devices
- Remove accessory equipment supplied with the machine



III. 1 Machine secured on square wooden supports and L-bars

- Attachment screws
- 5 Clamping screw
- Transverse wooden
- Machine foot
- supports
- L-bars
- 3 Longitudinal wooden supports
- Clamping element
- Crossbeam



III. 2 Machine foot

- Undo the clamping screws (5)
- Loosen all the clamping elements (8) using an SW 41 open-ended spanner and screw them out uniformly
- Put the machine down on the floor carefully
- Screw machine feet down to the floor where necessary
- Remove L-bars (7)
- Remove crossbeams (4)

Assembling the packaging machine

These instructions only need to be followed if the machine was delivered in parts.


If this is not the case, miss out this section and continue with the "Alignment" section.



Follow the Instructions

in the "Safety" section!

- Make sure there are wooden supports between the extension and the forks
- Lift the extension carefully with a fork-lift truck



III. 4 Extension with wooden support

Attachment of the extension

"Extension" means the extensions at the discharge end of the machine.

The instructions in this section can be disregarded if the machine does not have an extension.



III. 3 Extensions with wooden supports


important note!

The extension must not be allowed to lie on the forks - there is a danger that it might be dented.

- Position the extension at the discharge end of the machine. Danger that it may topple over! Put a wooden support underneath it*
- Align the extension with the machine

Fitting alignment sections


- Fit alignment sections (9) at the connection points
- Carefully join the parts of the machine together



III. 5 Joining the machine together


Depends on the machine configuration

- Insert and tighten screws (10) directly below the Plug all the plugs (14) in the distribution cabinet connection points




III. 6 Connection points

- Attach the metal bracket (12) with screws (11)
- Remove the wooden support*
- Align the machine in accordance with the instructions given later in this manual
- Connect hoses correctly by referring to their markings
- Connect the compressed air hoses for the cutting units



III. 7 Oil container for automatic chain lubrication

Connect the hoses for automatic chain lubrication (13) to the distributor in the main control cabinet



III. 8 Machine with distribution cabinet

Important note!

Never pull on the cables to remove the plugs. Do not use force when connecting plug-in connections.

- If there is a vacuum pump for forming, connect the cable in the terminal box of the pump.


Important note!

Check the direction of pump rotation before switching on the machine

- Connect the drive motor cable in the main control cabinet (see electrical wiring diagram)
- Connect the cables of the cutting units, the vacuum trim removal unit, the edge trim rewind unit etc. in the main control cabinet (see electrical wiring diagram)

Depends on the machine configuration

Fitting the rotary shaft encoder



III.9 Fitting the rotary shaft encoder

- Attach the rotary shaft encoder with screws (15); do not tighten them
- Put the toothed belt (16) on
- Tighten the toothed belt and the screws (instructions on this can be found in chapter 05 entitled "Advance drive - tightening the toothed belt")
- Fit the cables in the holders provided for this purpose and secure them with a plastic clip if necessary


Important note!

The cables must not touch the toothed belt

Connecting the magnetic reed switches

Connect the magnetic reed switches to the magnetic reed switch terminal strip in the main control cabinet (see the electrical wiring diagram).


Note the markings on the individual cables.



III. 13 Connection terminals in the main control cabinet


installation of the film transport chain

- Remove the chain guard (20)
- Undo the clamping screw (21)
- Move the sprocket wheel towards the centre of the machine by turning the tensioning screw (22) to the left



III. 11 Installation of the film transport chain

- Insert the chain into the chain guide rails on both sides and pull it towards the drive
- The ends of the chain (23) must be easily accessible




III. 12 Positioning of the ends of the chain

Pull the chain tight until the ends of the chain touch

Note:

Make sure the ends of the chain touch



III. 13 Assembly of the film transport chain


- Fit the chain link and the connecting link (24) together (red marking)
- Clamp the locking wire (25) in position
- Fit the chain clamp (26)
- Put on the spring (27)
- Tighten the chain in accordance with the description in chapter 15

Attachment of the discharge conveyor

Instructions on this can be found in the description of the discharge conveyor in chapter 05

Checking, fitting of guards, panels etc.

- Check the oil level of the pumps, central lubrication system and maintenance units
- Secure bars (28) at the connection points
- Fit the side panelling (28)
- Put in the support tray and the discharge plate
- Fit the die guards



III. 14 Fitting the side panelling

Alignment

- The machine does not need any foundations and does not have to be attached to the floor etc.
- Make sure there is easy access to the control cabinets


Note:

Always align the machine with a spirit level - a machine spirit level if one is available


- Align the machine horizontally in machine and cross direction using a spirit level (III. 15)
 - Undo the clamping screw (5)
 - Adjust the clamping element (8) using an open-ended spanner
 - Tighten the clamping screw (5)
 - Do not remove the clamping element (8) until the alignment process has been completed
 - Keep the L-bars and the clamping element for subsequent transport operations

Important note!

The machine can be damaged if it is not aligned properly.



III. 15 Alignment of the machine



III.16 Machine foot

Electrical connections

Mains connection



High voltage -Life in danger


Important instructions

- All work should be carried out by trained electricians
- Observe the relevant regulations and directives
- Connected load figures can be found on the nameplate
- Connect the mains cable in accordance with the information given on the terminals, making sure the electrical wiring diagrams are observed


Tolerance of the mains voltage \pm 10 %

Cross-section of the mains cable

Nominal current * A	25A	36A	50A	63A	80A
Cross-section mm ²	4	6	10	16	25



III. 17 Electrical connection



III. 18 Nameplate

Compressed air connections

Compressed air in the supply line

min 7 bar max 10 bar

Compressed air consumption

The compressed air consumption depends on the machine equipment and the operating speed (cycles per minute). A calculation can be made at the factory on request.

Characteristics of the compressed air

- Filter element 25 microns (to be fitted by the customer)
- Moisture content max 1 g/m³

Recommendation:

If there are temperatures of 3°C and higher in the compressed air network, the compressor should be followed by a refrigeration drier.


In the case of temperatures below 3°C, the compressor should be followed by an adsorption drier.

Installation

Lay a compressed air line of 3/4" to 1". Blow it out thoroughly before starting operation.

The standard compressed air connection is in the main control cabinet.

Depending on the machine equipment, there may be a further connection in the control cabinet at the infeed end of the machine (see III. 21).



III. 21 Maintenance unit

Setting

Operating air pressure: max 7 bar

Setting on the pressure regulation valve (30):

- Turning clockwise:
 Air pressure is increased
- Turning counter-clockwise: Air pressure is reduced

Notes

A pressure monitor is set in such a way when the machine is supplied that the machine stops when the pressure drops **below** 5 **bar**. The main valve (32) shuts the compressed air supply off completely, when the main switch is turned to 0.

This does not apply in particular to:

- Control valves for evacuation and forming
- Equipment for blowing out the water circuit

A fault message appears on the display

Amount of oil

Setting the amount of oil on the lubricator (31):

- Turning clockwise:
 Amount of oil is increased
- Turning counter-clockwise: Amount of oil is reduced

Approximate figure: about 1 drip/5 min.

Vacuum connections for external vacuum pumps

There are machine configurations which are designed for an external vacuum supply system. In such cases there may be one or more vacuum connections.

Important note!

Among other things, the shelf life of food packs depends on the maximum final vacuum level (and the nominal capacity) of the pump. Select suitable pumps.

General instructions


- Use only the special hose supplied with the machine as the vacuum line.
- Where possible, avoid sharp curves, corners and long supply lines. Every change in direction leads to a reduction in evacuation efficiency.
- Read the instruction manual supplied by the pump manufacturer before starting operation

Basic principles

External vacuum pumps should be located as close as possible to the machine. The vacuum hose should be no longer than 10 m at the most.

Location of the connection


The external vacuum connections are always near the places marked with an arrow in III. 22. Consult the connection diagram about this as well.



III. 22 Vacuum connections

Evacuation via a central vacuum system

In such cases there are **two** connections for evacuation on the sealing die. Note the distinction between APPROXIMATE/PRECISE vacuum (see chapter 09).



III. 23 Vacuum connections with a central vacuum system

A = Precise vacuum

B = Approximate vacuum

Evacuation with a Roots pump

A Roots pump must **not** be operated **without** a **backing pump**. The machine control system is designed in such a way that the Roots pump cannot start without the backing pump being switched on.


The connection line between the Roots pump and the backing pump is 1 1/2" or 2", depending on the size of the backing pump.

Bush Vacuum 54P Piece # 5 Seril # E20118

Cooling water connections

Requirements on the cooling water

- Max. inflow temperature 15°C
- Filter element 50 microns
- pH level 7 ... 7,5
- Content of:
 Iron (Fe) and manganese (Mn) < 0,1 mg/l
 Calcium (Ca) 22 ... 50 mg/l
 Magnesium (Mg) 13 ... 30 mg/l
 Free chlorine (Cl) < 0,1 mg/l



III. 24 Cooling water inflow and outflow

The water supply authorities responsible can provide information about water composition.

Cooling water requirement

180 - 300 I/hour of cooling water at 15°C are required, depending on die size and the built-in vacuum pumps.

Notes

- When installing new lines, use a nominal width of 1/2". Blow them out thoroughly before starting operation.
- Water outflow should be downwards to make sure that water left in the system does not flow back.
- If water costs are high, recooling in a selfcontained circuit may be more economic. This also reduces calcium deposits.

If processed (demineralized) water is to be used in a water circuit, the pH level needs to be checked regularly.

If the pH level is in the alkaline range (i.e. higher than 7,5), it is necessary to add e.g. powdered citric acid to prevent the formation of aluminium hydroxide Al(OH)³.

This would lead to deposits and - if the worst came to the worst - to blockage of the water lines.

The optimum pH level setting is between 6 and 7. Please consult MULTIVAC or its agent about installation of a recooling circuit.

Setting

Water pressure in the supply line: min 1,5 bar max 4.5 bar

Flow


The water flow volume is set at the factory based on a water inflow temperature of 10°C (see ill. 25)

Correction:

- + flow volume is increased
- flow volume is reduced

Note:

Condensation may form if the cooling water flow volume is too high. The die top should be so warm that it can still be touched.



III. 25 Regulation of water flow


A flow monitor is fitted in the outflow system (see III. 26)

It is set so that the machine stops when the flow volume is less than 2 l/min.

Do not change the setting of the flow monitor!

Shutting off the cooling water

Turn the main switch to 0
 A diaphragm valve shuts the water supply off.



III. 26 Water flow monitor

Gas connections

This section can be disregarded in the case of machines that do not have a gas flushing unit. Information on the kind/mixing ratio of the gas required can be obtained from your gas supplier or via the Multivac organisation.

î

III. 27 Gas connection

Location

The standard gas connection (34) is on the main control cabinet, Cross section of the gas supply pipe 1/2".

Safety



DANGER OF SUFFOCATION
DANGER OF EXPLOSION

- Observe the safety regulations
- input pressure must not exceed 7 bar
- Ventilate rooms well, avoid gas accumulation
- Shut off the gas supply when machine operation stops

Note:

The gases do not smell!

- When using oxygen:
- Do not smoke
- Make sure there is no oil and grease on parts such as fittings, valves and hoses through which gas flows
- Move flammable objects out of the room


Setting

Set the gas pressure on the precise gas regulation valve on the gas bottle (33):

max. 7 bar


On the precise gas regulation valve (35) in the main control cabinet:

Setting depends on the product and pack size.



III. 28 Precise gas regulation valve/gas connection

If there is a gas mixing unit (36), read the description of it in chapter 09.



III. 29 Gas connection with gas mixing unit

03 Transport, storage, installation, start-up/shut-down

Final checks

When all the preparations have been completed, check the following points again:

- Is compressed air available and is the compressor switched on?
- Is cooling water available and is the shut-off valve open?
- Is a water outflow facility (unpressurized) available?
- Is gas available* and is the shut-off valve open?

Oil level check

- Vacuum pump
- Maintenance unit
- Automatic chain lubrication system*

Grease level check

Automatic grease lubrication for the lifting unit*

If the packaging machine was delivered in parts

- Check the phase control in the main control cabinet
- Check the direction of rotation of the vacuum pumps*

Depends on the machine configuration

Appendix 6.3

Equipment Transportation Manual

R 530

Contents

- O Safety
- O Types of packaging/forms of transport
- Storage
- O Preparations for transport



III. 1 Transport by a fork-lift truck

Safety



Lifting of loads - Extremely dangerous!

- Observe the safety regulations
- Use suitable lifting equipment
- Note the weight information provided on the packaging or in the shipping documents
- Danger that the load may topple over Note where the centre of gravity is


Type of packaging/forms of transport

Machine unpackaged or protected with film (fork-lift truck, lorry)


- When new machines leave the factory, they are supported by an L-bar and wood construction
 The L-bars are essential for subsequent transport
- Position the forks of the fork-lift truck as far apart as possible
- Keep a particularly close eye on parts that project (e.g. film unwind unit, edge trim rewind unit, discharge conveyor)
- Never lift a machine by the discharge extension
- When using a fork-lift truck, approach the machine from the operator's side
- Determine the centre of gravity of the machine. It may not be in the middle of the machine

Carton (air freight) or wooden crate (sea freight)


- Lifting with a fork-lift truck: note the centre of gravity arrow
- Lifting with a lifting unit: note the chain symbols




III. 2 Machine with discharge end extension



III. 3 Unpackaged machine



III. 4 Machine lifted by a fork-lift truck



III. 5 Machine lifted by a lifting unit

Storage

Storage conditions

- In the original packaging or covered with a sheet of film
- Dry conditions
- Not in an aggressive atmosphere
- Never in temperatures below 0°C, as serious damage could be caused in the water circuit

Preparation for transport


- Undo all the clamping screws (3)
- Fit the clamping elements (4)
- Tighten the screws (5)
- Fit the L-bars (7) supplied with the machine from both sides


If they are no longer available:

- Prepare an L-bar with dimensions of at least 120 x 120 x 12 (length depends on the machine) for each side
 Make a slit for each foot (see III. 6)
- Screw the machine foot (6) on the clamping element (4) to the stop using an open-ended spanner

Note:

If a machine needs to be moved on frequent occasions, MULTIVAC can supply special foot supports (8). See the spare parts list for details.





III. 6 Fitting transport bars

Appendix 6.4

Equipment Set Up - Rutgers U. FMTF

PAGE 1

PRODUCT	MULTIVAC R530/635	8 LINE DISPLAY PROGRAM # TRACK X Z ROW MEMORY # 0
SELECTION FORMING DIE NR: 6 0 ALL FUNCTIONS OFF 6	ALUFOIL	OF WES FORMING DIE NR: // O ALL FUNCTIONS OFF 1 STANDARD
1 STANDARD 2 WITH PREHEATING 3 PLUG BEFORE AIR 4 AIR BEFORE PLUG 5 POSIFORM	DIE LIFTING	11 DIE LIFT OFF TIMERS: FORMING BOTTOM FILM TIMER #
SELECTION SEALING DIE NR: 3 O ALL FUNCTIONS OFF 6 NO SEALING DIE VACUUM TEST 7 NO SEALING DIE VACUUM SEALING DIE	/AC & GAS BY GAUGE + TR SPF DIE LIFT. OFF	0.00S DELAY AIR - PLUG 4 0.00S PREFORMING POSIFORM 6 0.00S DELAY PLUG RETURN 6 0.00S HEATING 16 0.00S FILL TIME 2 0.0S FORMING 17 0.75S FILL TIME 3 0.0S PLUG 18
TIMERS: FORMING TOF \[\frac{\partial}{0.0} \text{s HEATING} 40 <-\frac{\partial}{0} \] \[\frac{\partial}{0.0} \text{s FORMING} 41 <-\frac{\partial}{0} \]	FILM TIMER #	THE CHATION 25
TIMERS: OTHERS	TIMER 4	6 2.2 s SAFETY TIME SEALING 2.2 s SAFETY TIME SEALING 2.3 o s DELAY SEAL TO VENTILATION 3.7 1.0 s DELAY CUTTING 3.6 s CUTTING 3.6 s CUTTING 47
ZONE O PRE-HEATING TOP WEB HEATING STEAM 4 SKIN 5 SEALING	O 10	TEMPERATURE: VALUES Xp(%)TV(s) ** STOP ZONE Xp TV ** 0 5.0 20 ** 10 0 1 5.0 20 ** /0 0 2 5.0 20 ** /0 0 3 5.0 20 ** /0 0 3 5.0 20 ** /0 0 0 4 5.0 20 ** /0 0 0 5.0 20 ** /0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0
ZONE 6 SEALING 1 7 SEALING 2 8 SEALING 3 9 SEALING 4 10 11 COOLING WATER	TURE MONITOR SET - 230 /0 230 /0 230 /0 230 /0 10 30 /0	+ STOP CHANNEL ACTUAL 10

						P	AGE 2
DATE:	AMERIQUAL 5/12/98 PRODUCT	MULTIVA R530/63		8 LINE DISP # TRACK X_2			0
0 1= / LO	FUNCTIONS : ON/O REGISTER MARK CONTROL ADVANCE, 0=BRAKE ADING GRID	: OCUTTIN	G ORP2	REG	ULATC : SSURE		PSI
/ AI	OP: 0=DIE, 1=ADVANCE R CLAMP. FORMING DIE D MEAT PROGRAM OWING CHAIN	/ CUTTIN / CUTTIN / SYNC. / SYNC.	G STS2	SEAL PRESSUR			•
	FUNCTIONS 2: ON/O	FF				<u> </u>	
/ HO	OLING STATION OLE PUNCH PUNCH TOP / 1=PUNCH B R CLAMPING FORMING DI		0 0 0 0				
1 CH 2 LU 3 CY 4 CY	COUNTER R/S REASE RAIN LUBRICATION RESERVED RUN CLES RESETTABLE CLES TOTAL PERATION TIME		TING 5000 500 208	C EDGE TRIM	OUNTE!	R 2 SETTI _2	
DIE S REGIS		mm	0.5s 5.5s 5.5s	SYNCHRONIZAT SYNC 1 OUTPUT SYNC 2 OUTPUT SYNC 3 OUTPUT WAIT FOR SYNC T FOR SYNC 2 1 : NO/YES	, PUL: , PUL: , DEL:	SE WIDTH AYED BACK	34 35 32
				DIE LIFT	ING		
			CUSI	NING GAP FORMI NING GAP SEALI NING GAP TOP Ø HIONING AY CUSHIONING	Ú. C	Oy s	3
NCTES	3:						

FORMING DEPTH ____mm SEALING DEPTH ____mm

Appendix 6.5

Equipment Data Sheets; Multivac R530 Set Up, Program Log, QC Record

R530/645 8 LINE DISPLAY PROGRAM
4 TRACK X 2 POW DATE: PRODUCT 4 TRACK X 2 ROW MEMORY # SELECTION FORMING DIE TOP WEB FORMING DIE NR: O ALL FUNCTIONS OFF 6 ALUFOIL 0 ALL FUNCTIONS OFF 1 STANDARD 1 STANDARD 2 WITH PREHEATING 3 PLUG BEFORE AIR 4 AIR BEFORE PLUG 11 DIE LIFTING 5 POSIFORM OFF 11 DIE LIFT OFF SELECTION SEALING DIE TIMERS: FORMING BOTTOM FILM NR: O ALL FUNCTIONS OFF 6 VAC & GAS _._s DELAY AIR - PLUG _._s PREFORMING POSIFORM 1 VACUUM TEST BY GAUGE + TR 2 EVAC. TIMER CONTROLLED _ s DELAY PLUG RETURN ____ S HEATING 16 ____ S FILL TIME 2
___ S FORMING 17 ___ S FILL TIME 3 4 SKIN, SHRINK 11 DIE LIFTING 5 VAC & GAS BY TIMER OFF _._s PLUG 18 TIMERS: FORMING TOP FILM TIMER: EVAC., GAS, SEALING 1 TIMER # TIMER # _____ S HEATING 40 <- ____ S FILL 11 ____ S FORMING 41 <- ___ S FILL 12 _._s EVACUATION 25 __s GASING _._s SEALING 0.Cs _._s DELAY SHRINKING 14 _._s SHRINKING 15 TIMERS: OTHERS TIMER: OTHERS TIMER # TIMER # _ s SAFETY TIME FORMING 19
_ s SAFETY TIME SEALING 21 280 s GREASE 46 21 _ s DELAY SEAL TO VENTILATION 28 _ s DELAY CUTTING _._ s CUTTING 38 _._s DIAGNOSTIC TIME TEMPERATURE TEMPERATURE: VALUES Xp(%) Tv(s) ZONE SET -+ STOP ZONE Xp Tv O PRE-HEATING 0 5.0 20 0 10 10 5.0 20 2 TOP WEB HEATING 2 5.0 20 3 5.0 20 0 10 10 0 0 10 10 0 0 10 13 3 5.0 4 5.0 20 5 SEALING 5 5.0 20 TEMPERATURE MONITOR SENSORS + STOP CHANNEL ACTUAL ZONE SET -6 SEALING 1 12 VAC SENSOR VAC 7 SEALING 2 13 PRE-VENT. 14 ----8 SEALING 3 9 SEALING 4 15 SEAL PRESSURE ___MIN_

0 10

11 COOLING WATER

10

MULTIVAC

WORNICK COMPANY R530/640 DATE: PRODUCT	8 LINE DISPLAY PROGRAM 4 TRACK X 2 ROW MEMORY
FUNCTIONS : ON/OFF REGISTER MARK CONTROL: 1=ADVANCE, 0=BRAKE CUTTING QRP1 LOADING GRID CUTTING QRP2 STOP: 0=DIE, 1=ADVANCE CUTTING STS1 AIR CLAMP. FORMING DIE CUTTING STS2 RED MEAT PROGRAM SYNC. 1 BLOWING CHAIN SYNC. 2	REGULATORS MAIN AIR PRESSURE 90 PSI SEAL PRESSURE 25Y1 BAR THROTTLE VACUUM REGULATOR
FUNCTIONS 2: ON/CFF COOLING STATION 0 HOLE PUNCH 0 O=PUNCH TOP / 1=PUNCH BOTTOM 0 AIR CLAMPING FORMING DIE TOP WEB 0 0 - 0 - 0	
COUNTER NO. R/S ACTUAL SETTING O GREASE 1 CHAIN LUBRICATION 2 LUBRICATION RUN 3 CYCLES RESETTABLE 4 CYCLES TOTAL 5 OPERATION TIME	COUNTER 2 SETTING EDGE TRIM STOP
ADVANCEmms SPEED	SYNCHRONIZATION SYNC 1 OUTPUT, PULSE WIDTH 33 SYNC 2 OUTPUT, PULSE WIDTH 34 SYNC 3 OUTPUT, DELAYED 35 WAIT FOR SYNC FEEDBACK 32 T FOR SYNC 2 WITH CLOSED DIE ? 1 : NO/YES DIE LIFTING HING GAP FORMING DIE (1 - 8) HING GAP SEALING DIE (1 - 8)
OPEN CUSH	UING GAP SEALING DIR (1 - 8) UING GAP TOP WEB (1 - 8) UING GAP TOP WEB (1 - 8) UING GAP TOP WEB (1 - 8) UING GAP SEALING DIR (1 - 8) UING GAP TOP WEB (
FORMING DEPTHmm SEALING DEPTH mm	

Multivac Program Log

Program #	Application	Comments	Date Modified
the second second			
	:		
		The state of the s	
	1		
	1		
*		•	
		·	
	1		
WARE			
	** ** *** *** *** *** *** *** *** ***		
	······································		
	-		

Date: 2/10/99 Supersedes: New

		T		
Multivac Record				
Multivac program number			1	
Cycle rate (cycle/min)				Programme and the second
Bottom web lot number				
Top web lot number				
Pouch volume (cc)				
Pouch depth (mm)		t to the second		
Forming program number				
Forming time (sec)				
Forming fill time (sec)				
Advance speed				
Advance acceleration				
Sealing program number				
Vacuum (millibar)				
Vacuum chamber pre-vent (millibar)				
Gas flush (millibar)				
Sealing temperature ©				
Sealing time (sec)				
Sealing pressure (bar)				
Retort crate number		1		
Retort crate start fill time				


Date: 2/10/99 Supersedes: New

Approximate residual gas (cc)		
Number of pouches produced		
Number of pouches to QC		
Pouches to retort (include IT sample)		


Multivac Installation Photos




Sealing/Punch Section




Joining Sections




Machine Aligned and Leveled




Making Connections




Installing Top Web Forming Station




Primary Vacuum Pump




Roots Blower



Accessories on shipping pallets




Installing Chains



Appendix 6.6

Wooden Shipping Pallets and Steel Shipping Bars



Appendix 6.7

Lawson-Marden Singen: Flexalcon Technical Information (Packaging Rollstock)

Terms for technical prerequisites and processing conditions for Flexalcon packing system on the Multivac R 530

Layout of the form tool

1.1. Packing format (right-angled)

Outer measurements Inner measurements

1.2. Form depth

Maximum 25% of the narrow package inner measurement (measured at the sealing edge inner rim) which corresponds to a maximum forming depth of ...

- **1.3.** Angle of the slope (angle of the side surface) $> 45^{\circ}$
- 1.4. Radii and transitions (joining radii): Minimum 20 mm radius

2. Forming conditions

Forming pressure

28 PSI - 43 PSI (2 - 3 bar)

Forming time

2 - 3 seconds

3. Evacuation

Remaining vacuum

≥ (50 mbar) 0,7 PSI

4. Sealing conditions

(Sealing) temperature

max. $(230^{\circ}C) = 450^{\circ}F$

Time

< 2 seconds

Pressure

(4.5 - 5 bar) 64 PSI - 70 PSI

5. Sterilizing conditions

Max. (125°C) 260°F / 30 - 60 minutes / max. 40 PSI(max. 2.8 bar) in counterpressure steam autoclave

6. Colour tone change caused by sterilization

Discoloration and markings may occur on the package as a result of the sterilization process. These occurrences are normal and do not effect the performance of the package.

Il Transport, storage and handling conditions

1. Transport

• Temperature (short-term) max. 105F° (40°C)

To be protected from frost

• Relative air humidity max. 90%

2. Storage

Maximum one year at a temperature of 60 - 85°F (15 - 30°C)

• Relative air humidity 30 - 70%

Before processing the material store it for 48 hours in the climatic conditions of the production area.

3. Handling

Reels are delivered in vertical position. Upon turning the reels, care must be taken to protect the reel edges and web from damage and abrasions. The required equipment should be available.

III Filling conditions

1. Sealing zones

It is of utmost importance to ensure that the sealing zones are completely unsoiled during the filling process.

2. Position of the filling products

For solid and paste fillings It is important to place the products in the **center** of the mould of the bottom material.

3. Package impermeability

The impermeability of the package is checked through the bursting pressure test (Wornick method) (> 30 PSI)

The test is carried out on empty packages, which are to be taken from every web at the start of production, at every half an hour during the production and at each change of reel.

4. Filling product

Solid and paste products No frozen products should be packed, as this might lead to cut-throughs.

IV Action when processing difficulties occur

When difficulties occur which can be attributed to the packing material, production with the reel(s) in question must be stopped immediately until the causes have been clarified definitely.

In this case the production should be continued with another reel.

LAWSON MARDON FLEXALCON PACKING SYSTEM Film/Foil Structures for U.S. – Military Applications –

Top material:

19my PET/12 my AI/75 my PP

Bottom material:

30 my OPP/45 my AI/15 my OPA/75 my PP

Lawson mardon Singen GmbH 01.07.1999

Appendix 6.8

Multivac R530/#645 Machine Card and Tooling

M U L T I V A C Maschinenkarte extern	Kunde AMERIQUAL/MRE PROJEC	Auftrags-Nr.: 440.48597 Stuli-Nr. : 04.404.8597.000.0
Vertretung: MU-INC.	Typ : R 530 MC	MEAG-Nr. : 1995-01529 Bestell-Nr. : 990116
LKZ : 731 02 PKZ : 390	Masch-Nr. : 645	Bestell-Dat.: 17.05.95
	Baujahr : 95 Spannung : 220V/60HZ	Ausstell-Dat: 10.07.95 HAG RD Blatt : 1
	Beschriftung: ENGLISCH	

Versandart: SEEFRACHT

Verpackung:

Änderungen: A 3.08.95 HA RD B 19.09.95 HA RD C 21.09.95 HA RD D 26.09.95 HA RD

E 6.10.95 HA RD F 5.12.95 HA RD

Ä Po	s S	Beschreibung	Preislisten-Nr.
00:	1 :	1 R 530 basic machine 12375 mm frame length tot. MC92-Control	В
002	_	Frame lngth 10875mm WZA 78408640 mm KF 6525 mm Cladding in knee-free area	B. 0.03.01 B. 1.02.10 B. 1.09.00
004	4	Special web width 535 mm	B. 2.01.07
005	5	2600 mm discharge - cross cut area 2050 mm - roller shear cut 160 -	B. 3.02.04
006	5	Pneumatic control cabinet - infeed end -	B. 4.04.00
007	7	Safety standards System D with magnetic switches - MSG single built-in / with photoelectric beam -	B. 5.03.00
008	3	Cover guard SF for tunnel at machine discharge - with finger curtain -	B. 5.03.03
009)	Safety guards	A. 5.03.09
010)	Die lift.system A: stroke 170 mm / sgl.lift FWZ	B. 6.01.00
		4-post lift.mechanism / post centers 550 mm Lifting mechanism for Forming - System A -	B. 6.01.01
		4-post lift.mechanism / post centers 550 mm 170 mm maximum stroke / UT lower part real mm Lifting rail position mm	
D 011 D	1	Add.lifting mechanism for Forming - System A -	B. 6.05.01
D D D		4-post lift.mechanism / post centers 550 mm 170 mm maximum stroke / UT lower part real mm Lifting rail position mm	

	AMER	IQUAL/MRE PROJECT	440.48597	04.404.8597.000	Blatt
Ä	Pos	St	Beschreibung		Preislisten-Nr.
		Hubwerks mit o nenbett zur Ve Anschlüsse übe Formluft, Luft	säulen Sonderanschluβbd benliegendem Kni rformung nach oh r Schläuche (Küh zum Heizen)	ock zur Montage des iehebel auf Maschi- oen alwasser, Formvakuu chlußbock integrier	m,
	012	4-post lift.mecha 60 mm OT upper	m for Sealing - 	System Bs. 550 mm part real mm	B. 6.02.10 B. 6.02.14
	013	MC92-Drive			B. 7.04.00
	014	Pneumatic equipm	ment for machin	ne 	A.19.00.00
			tant / for aggre top web adjustment rator with contr	products essive products colled drain valve	B. 8.08.10
		to pack cold pr			
		for later use	Valve		B. 8.08.11
		Forming System C	(Plug-assist D	ie)	B.10.03.00
		Heating and forming also for standar		air and vacuum	B.10.03.02
3 (015	1 Equipment for sep. for FWZ 1 x for top web	. closing pressu for 4-post	re - System R 530 lifting mechanism	B.10.09.01
		Preumatic accessor			Y.19.00.00
0)16	1 further comp.air 1 - incl. magnetic v	ubricator/regula alve -	ator	A.19.09.01

bei FWZ

2

Vacuum main valve UV 4/1.1 water-proof - for narrow/wide top web - add. valve for separate product vacuum 1 add. Wabco-Valve / 1 Wabco 5/2-Ventil für Hubmechanik Einlegeschablone 1 Vacuum pump RA 0100(-131) capacity 100 m3/h - built-in 3x220/380-415V/50-60Hz 3,00 kW for forming and top web forming	Y.19.24.12 A.19.24.01 Y.19.29.20 A.19.08.02 X.11.02.00
- for narrow/wide top web - add. valve for separate product vacuum 1 add. Wabco-Valve / 1 Wabco 5/2-Ventil für Hubmechanik Einlegeschablone 1 Vacuum pump RA 0100(-131) capacity 100 m3/h - built-in 3x220/380-415V/50-60Hz 3,00 kW	A.19.24.01 Y.19.29.20 A.19.08.02
<pre>1 add. Wabco-Valve / 1 Wabco 5/2-Ventil für Hubmechanik Einlegeschablone 1 Vacuum pump RA 0100(-131) capacity 100 m3/h - built-in 3x220/380-415V/50-60Hz 3,00 kW</pre>	Y.19.29.20 A.19.08.02
<pre>1 Wabco 5/2-Ventil für Hubmechanik Einlegeschablone 1 Vacuum pump RA 0100(-131) capacity 100 m3/h - built-in 3x220/380-415V/50-60Hz 3,00 kW</pre>	A.19.08.02
- built-in 3x220/380-415V/50-60Hz 3,00 kW	X.11.02.00
· · · · · · · · · · · · · · · · · · ·	
1 Mounting kit A) for vacuum pump: 100-131	B.29.10.01
	B.29.10.03
Noise muffler and common air discharge from compressed air operated units mit Anschluβ zum Herausführen der Abluft aus Verpackungsraum	A.12.01.00
3 Central lubrication system for die lift.sys. R 530	B.12.03.08
Stainless steel gripper chain covers	B.12.02.01
Gripper chain lubricator with cleaning unit - cycled action at preselected intervals incl.program for lubrication cycle	B.12.03.05
1 Additional guide roller for top web for inkjet with traversing unit	B.14.04.01
<pre>- mech. web-feed - 76 mm / 3 inches - max. Rollengewicht 80 kg</pre>	B.14.02.04
1 Tandem film unwind FA02 bottom web 535 mm 1 - mech. web-feed - 76 mm / 3 inches	B.14.06.04
	<pre>1 Mounting kit C) for Roots pumps: WV1000 siehe beil. Pumpenzeichnung Rootspumpe wird von MU-INC. besorgt Noise muffler and common air discharge from compressed air operated units mit Anschluβ zum Herausführen der Abluft aus Verpackungsraum 3 Central lubrication system for die lift.sys. R 530 Stainless steel gripper chain covers Gripper chain lubricator with cleaning unit - cycled action at preselected intervals incl.program for lubrication cycle 1 Additional guide roller for top web for inkjet with traversing unit 1 Tandem film unwind FA03 top web 535 mm - mech. web-feed - 76 mm / 3 inches - max. Rollengewicht 80 kg inkl. 6"-Adapter</pre> 1 Tandem film unwind FA02 bottom web 535 mm

IQUAI

	AMER	IQUAL/MRE PROJECT	440.4859 [†]	04.404.8597.000	Blatt 4
7.	Pos	St	Beschreibung		Preislisten-Nr.
	•				
	029 0 30	1 MC92 temp.control add. temp.control	l module for ma	ax.6 control loops	A.17.21.00 B.17.22.01
	031	1 Sensor for monito	oring cooling v	vater temperature	B.17.22.01
	032	7 Hardware per cont 1 x heating 1 x heating top 1 x sealing 4 x temperature	trolled heating	g circuit	B.17.23.00
	033	1 Analog pressure t			B.17.29.01
	034	1 Pressure transduct	cuum and/or ga	s flushing	B. 8.10.07
	035	1 RS 232 Interface		<u> </u>	B.17.31.01
		- up to 32 differ	ent batches -	g machine settings	A.17.20.06
	0 36	Reinigungsprogram	m für Maschine	R 530	B.18.79.03
		zum separaten A	n 1 auf 2 STS 2 QRP (zur spä bschalten des eschaltetem Zu	teren Verwendung) STS-Oberhubs, damit stand entweder ange-	B.18.30.03
		1 Key switch for MC - authorization for	-92-terminal or parameter ac	ccess	A.18.30.05
	037	1 Protrusion detecto	or KV1 for prod	duct above web line	B.18.14.00
		Durchlaβhöhe 30 Bei Packungen m: in "Oben-Stellur	it OFO-Verformu	ung wird Schaltblech	<i>,</i>
	038	Control cabinet he	eater		B.18.16.00
	039	Sychronisation for	infeed		B.18.51.00
		Anodizing of die -	die tops and	bottoms	A.22.26.00
B B	040	1 Die set /	die no. 33868-	300 /	A.21.11.00
В		- for sealing carr	iage (w/o carr	iage) -	
В		designed for alu	minum forming		
ВВ		535 mm bottom we 1 tracks 420 mm C/O lengt 185 mm die heigh	1 r h 105,5 m	m top web ows m die depth m die height SDA	A.21.12.00

185 mm die height FDA 185 mm die height SDA

external package size PM 496 x 416,5 mm

12 mm step height SDA

A.21.12.01

12 mm step height FDA

	AMER	IQUAL/MRE PROJECT 440.48597 04.404.8597.000	Blatt	5
Ä	Pos	St Beschreibung	Preislisten-Nr.	
		internal pocket size FM 481 x 398,5 mm	A.21.12.02	
		edge evacuation and gas flushing rod heaters	A.21.35.04 A.21.39.02	
		FDA-UP built to take grid, w/o grid Compressed air + vacuum forming with plug-assist - direct-acting cylinders - ZT 70 mm	A.22.26.06 A.22.10.04	
		non-heated plugs - semi-rigid film - Chrome handles - FDA-LP without radius plates FDA-LP without filler plates FDA-LP to take forming plates	X.22.10.04 A.22.22.02 A.22.36.03 A.22.36.05 A.22.36.07	
ВВ		w/o forming plate for basic die SDA - with evacuation - SDA-UP built to take sealing carriage - w/o sealing carriage for basic die -	A.24.00.06 A.24.24.02	
В		Chrome handels - high blocks - SDA-LP - SDA-LP without radius plates SDA-LP without filler plates SWZ-UT built to take sealing grid without grid -	A.24.22.02 — A.24.35.14 A.24.36.02 A.24.36.05 A.24.36.07	
CCC	080	New design forming plate FDA 01) 1 Forming plate - type 1 / F D A - L P 1 tracks 1 rows / No. 01) for basic die 33868- 300 FM 481 x 398.5 x 100 / PM 496 x 416,5 mm	- X.23.33.01 - -	4
_	041	carriage - anodized - 1 Seal plate carriage SDA-UP / Die No. 33869- 300 / - incl.spare sealing plate - 14) to suit Vario 1 / No. R530-33868/1 535 mm bottom web 535 mm top web 4 tracks 2 rows 420 mm C/O length 12 mm step height SDA	X.25.08.11 02 X.25.01.14	5
		PM 121 x 206,5 mm FM 106 x 188,5 mm SDA-UP heaters: cal rod heaters Aufreiβschlitz SWZ-OT verstärkt zur Aufnahme von dicken Siegelplatten - erforderlich ab Produktüber- stand >10 mm	X.25.10.10	

stand >10 mm

Kühlplatten auf Buchsen

glatt, zur Herstellung von Vakuumpackungen

auch verwendbar als Begrenzungspiatte für flexible Folie

В

1 Divider with set of plates R 20 / F D A - L P X.23.31.21 С 4 tracks 2 rows / No. R530-33868/4 (neu) С FM 106 x 188,5 mm / PM 121 x 206,5 mm С 21) for basic die 33868- 300 / Vario 2

B.27.24.01

B.27.25.01

X.12.04.13

Die guard pos. 4: SDA-discharge

4 Stainless steel loading grid with lift

to suit subdivision 1 / no. R530-33868/1

Innenmaße ringsum 7,5 mm kleiner als FM

Guard position 5: R 530

über je 3 Takte reichend

Eintauchtiefe ca. 5 mm

055

	AMER	QUAL/MRE PROJECT	440.48597	04.404.2397.300	Blatt	8
Ä	Pos	St	Beschreibung		Preislisten-Nr.	
	056	4 lifting mechanism stroke 50 mm for max. produc	n for loading gri		X.12.04.05	
		cycles per minute product:	e 15 cycles/min.		A.21.12.05 A.21.12.04	
		Reis mit Fleich alle Produkte i	ratin, Gemüse mi	ie verpackt		
		specification - be 25-35 my PP / 3	ottom web: 8-45my Alu / 75-	100 my PP	A.21.12.07	
		specification - to momentan ungefor 12 my PET/9-8my		P	A.21.12.06	
	057	1 Forming die upper	part / die no. :	33868- 301 /	A.22.20.00	
		535 mm bottom we 1 tracks 420 mm C/O lengt PM 496 x 416,5	l rov th 12 mm	vs step height FDA	X.22.20.00	
		single heating - a rod heaters	above -		A.22.01.01 A.21.39.02	
		Compressed air for w/o plug-assist - Comp.air + vacuum without plug-assis Heating plate FWZ-	<pre>flexible film - forming t - flexible fil</pre>	m - k heating -	A.22.10.00 Y.22.10.00 A.22.10.00 Y.22.10.00 A.22.27.03	
		FDA-UP heaters: ca	l rod heaters		A.23.10.00	
		new design SDA-LP			X.25.02.19	
()58	2 Matched male/female Special execution with pneum. direct and separate pneum	n ct drive for cut	ting lift	A.42.10.06	
		top lifter for mate for punch out a 3,	ched m/f punch ,5 mm strip in c	ross direction	A.42.10.09 A.42.10.09	
C	59	2 Cutting tool for m. to suit R530-33868/	./f. punch STS92 /1 / Vario 1	/ w.w. 535 mm	X.42.11.16	

to suit R530-33868/1 / Vario 1


	ahilk	IQUAL/MRE PROJECT	440.48597	04.404.8597.000	Blat	.t 9
Ä	Pos	St	Beschreibung		Preislisten-Nr	
		with integra	ated punch of tear	slit		
	060 061	l Roller shear (4 tracks -	cutting - basic uncutting shaft set to suit R530-33868 for use with Die N	ZT 160 B/1 / Vario 1 No. 33869- 300	X.47.40.00 X.47.41.14	
	062 063	3 Set of blades	s for edge trim ZT for 4 mm strip cut n -	160 E ZT 160	X.47.42.14 X.47.44.14	
	064	mit Randstre schalter	n rewind RSW.E3 wit eifenabriβkontrolle op bei Streifenabri	e mit Näherungs-	B.48.02.01	
	065 084	1 Punch cover fo nur für Aufr	nit for edge and m r vacuum removal c eiβkerben ubsauger wird vom	of punch waste	A.48.04.00 B.48.11.01	
В	066	Plexiglas drum for product	D 150 / middle tr height 30 mm	im strip removal	B.48.05.00	
	067	1 plexiglas drum			A.48.05.01	
E E E E		for moving 2 i - mounted in M to suit die incl.safety co	ordinator unit inc nkjet heads cross ultiprint area No. 33868- 300 / ver, magnetic swit O, to be delivered	the machine	A.53.02.02	052
(069	- height adjus covering 2 c			B.52.01.02	
C	070	1 Discharge conve	eyor synchr. 800 mr reyor -	n w.neoprene belt	B.55.08.00 A.55.19.02	
C	071	l Fork lift to ea mit Aufnahmep zum einfacher	ase die changes Dlatte aus Kunststo n Wechseln der OF-F	off Formstation	B.64.21.00	
0	72	spare rod heate for sealing pla	ers te die no. 33869-	300	X.95.10.14	
0	73*	spare rod heate for top web for Nr. 33868-302	ming station die n		A.95.10.06	

	AMERI	QUAL/MRE PROJECT	440.48597	04.404.51 .00	Blatt	10
Ä	Pos	St	Beschreibung		Preislisten-Nr.	
	074*	l add.sealing gas			X.95.16.10	
	075*	Extras 1 : 1 cov	rag Nr. 240.5.169 ver plate for ng station, with N		A.95.18.01	
B B B B	082*	ausgenommen fü	s. Satz Platten In Siegeleinschub Ir OF-Verformung I Juchsen und Schrau	2 mm	A.95.18.02	
ВВ	083*	Extras 3 : 1 Hub für Kühlvorric	mechanik htung mit Oberhub	60 mm	A.95.18.03	
	076	spare rod heater heating plate di			A.95.10.01	
	077 078 079	3 Operator manuals CE-Schild CE-Konformitätse	rklärung		A.28.91.08 M.95.90.08 M.95.90.08	

Additional Equipment Provided by Domestic Vendors

- 1ea. VideoJet Excel Series 273se 2 Head Ink Jet Printer
 - * traversing system part of R530
 - Spare Parts Kit
 - Compressed Air Filter System
 - Alert Light
 - Console Stand
- 1 ea: Ames Engineering Web Lift Model AWL8C "Backsaver H"
- 1 ea. Busch Inc. Model RA0400 Vacuum Pump for seal die evacuation
- l ea. Busch Inc. Model WV1000 Roots Blower to assist RA0400 Blower internally mounted in R530 at installation

if your man Manine Like weren't famine ment



Appendix 6.9

Multivac R530/#667 Machine Card and Tooling

M U L T I V A C Maschinenkarte extern	Kunde LAND O'FROST/MRE PRO	Auftrags-Nr.: 440.48601 Stuli-Nr. : 04.404.8601.000.0
Vertretung: MU-INC.	Typ : R 530 MC	MEAG-Nr. : 1995-01528 Bestell-Nr. : 990115
LKZ : 731 02 PKZ : 390	Masch-Nr. : 667	Bestell-Dat.: 17.05.95
ERZ : 390	Baujahr : 95	Ausstell-Dat: 10.07.95 HAG RD
	Spannung : 220V/60HZ	Blatt : 1
	Beschriftung: ENGLISCH	

Versandart: SEEFRACHT

Verpackung:

Änderungen: A 28.07.95 HA RD B 6.09.95 HA WM C 15.09.95 HA RD D 26.09.95 HA RD

E 6.10.95 HA RD F 23.10.95 HA RD G 6.12.95 HA RD

A	Pos St	Beschreibung	Preislisten-Nr.
	001 1	R 530 basic machine 12375 mm frame length tot.	В
		MC92-Control	B. 0.03.01
	002*	Frame lngth 10875mm WZA 78408640 mm KF 6525 mm	B. 1.02.10
	003	Cladding in knee-free area	B. 1.09.00
	004	Special web width 585 mm	B. 2.01.07
	005	2600 mm discharge - cross cut area 2050 mm	B. 3.02.04
		- roller shear cut 160 -	
	006	Pneumatic control cabinet - infeed end -	B. 4.04.00
	007	Safety standards System D with magnetic switches	B. 5.03.00
		- MSG single built-in / with photoelectric beam -	D. 5.05.00
	800	Cover guard SF for tunnel at machine discharge	B. 5.03.03
		- with finger curtain -	D. 3.03.03
	009	Safety guards	A. 5.03.09
	010	Die lift.system A: stroke 170 mm / sgl.lift FWZ	B. 6.01.00
		4-post lift.mechanism / post centers 550 mm	
		Lifting mechanism for Forming - System A -	B. 6.01.01
		***************************************	2. 0.01.01
		4-post lift.mechanism / post centers 550 mm	
		170 mm maximum stroke / UT lower part real mm Lifting rail position mm	
ת	011 1	Add lifting makening for Francisco Control	D. C. O.S. O.S.
D		Add.lifting mechanism for Forming - System A -	B. 6.05.01
D		4-post lift.mechanism / post centers 550 mm	
D D	20.00	170 mm maximum stroke / UT lower part real mm Lifting rail position mm	
		,	

Ä Pos	St Beschreibung	Preislisten-Nr.
	Vacuum main valve UV 4/1.1 water-proof - for narrow/wide top web -	Y.19.24.12
	add. valve for separate product vacuum	A.19.24.01
	1 add. Wabco-Valve /	Y.19.29.20
	1 Wabco 5/2-Ventil für Hubmechanik Einlegeschablone	A.19.08.02
017	1 Vacuum pump RA 0100(-131) capacity 100 m3/h - built-in 3x220/380-415V/50-60Hz 3,00 kW for forming and top web forming	X.11.02.00
018	1 Mounting kit A) for vacuum pump: 100-131	B.29.10.01
019	1 Mounting kit C) for Roots pumps: WV1000	B.29.10.03
	siehe beil. Pumpenzeichnung Rootspumpe wird von MU-INC. besorgt	5.25.10.03
020	Noise muffler and common air discharge from compressed air operated units	A.12.01.00
	mit Anschluβ zum Herausführen der Abluft aus Verpackungsraum	
021	3 Central lubrication system for die lift.sys. R 530	B.12.03.08
022	Stainless steel gripper chain covers	B.12.02.01
023	Gripper chain lubricator with cleaning unit	B.12.03.05
	- cycled action at preselected intervals incl.program for lubrication cycle	
C C	l Additional guide roller for top web for ink jet with traversing unit	B.14.04.01 014
A 024 A A A	<pre>1 Tandem film unwind FA03 top web 585 mm - mech. web-feed - 76 πm / 3 inches - max. Rollengewicht 80 kg inkl. 6"-Adapter</pre>	B.14.02.04
A 025 A A A	<pre>1 Tandem film unwind FA02 bottom web 585 mm - mech. web-feed - 76 mm / 3 inches max. Rollengewicht 80 kg inkl. 6"-Adapter</pre>	B.14.06.04
026	Electrics and Electronics	
	3-phase AC 220 V without neutral wire 60 Hz	Y.15.01.01
027	<pre>1 Photoelectric registration for top web only to be used with non-formed top web</pre>	B.16.01.00
028 C	1 MC92-Terminal with fluorescent screen 42 character, 8 line display on separate post on machine frame	A.17.20.02

Ä	Pos	St Beschreibung	Preislisten-Nr.
_			TECTSTISCENT.
	029 030 031 032	1 MC92 temp.control module for max.6 control loops 1 add. temp. control module for 6 control loops 1 Sensor for monitoring cooling water temperature 7 Hardware per controlled heating circuit 1 x heating 1 x heating top web forming	A.17.21.00 B.17.22.01 B.17.22.05 B.17.23.00
		<pre>1 x sealing 4 x temperature control sealing plate</pre>	
	033	l Analog pressure transducer monitor sealing pressure	B.17.29.01
	034	<pre>1 Pressure transducer for display and control of vacuum and/or gas flushing</pre>	B. 8.10.07
	035	1 RS 232 Interface with Slave MC92 storage module f.memorizing machine settings	3.17.31.01 A.17.20.36
	036	- up to 32 different batches - Reinigungsprogramm für Maschine R 530	B.18.79.03
		3 Add.on-off/selector function per VFT sum Schalten von 1 auf 2 STS oder von 1 auf 2 QRP (sur späteren Verwendung) sum separaten Abschalten des STS-Oberhubs, damit die STS in ausgeschaltetem Zustand entweder ange- hoben oder abgesenkt stehen bleiben kann	B.18.30.93
		<pre>1 Key switch for MC-92-terminal - authorization for parameter access</pre>	A.18.30.05
	037	1 Protrusion detector KV1 for product above web line	B.18.14.00
		Durchlaβhöhe 30 mm beachten Bei Packungen mit OFO-Verformung wird Schaltblech in 'Oben-Stellung" arretiert	
	038	Control cabinet heater	5.18.16.00
	039	Sychronisation for infeed	B.18.51.00
СС	040	Anodizing of die - die tops and bottoms New design STMP/WZ-HRT 1 D i e s e t / die no. 33866- 300 /	A.22.26.00 Y.80.01.04 A.21.11.00
C		- for sealing carriage (w/o carriage) -	
C		designed for aluminum forming	
C C		585 mm bottom web 585 mm top web 1 tracks 1 rows 375 mm C/O length 105,5 mm die depth 185 mm die height FDA 185 mm die height SDA 12 mm step height FDA 12 mm step height SDA	A.21.12.00

Ä	Pos	St	Beschreibung	Preislisten-Nr.
			Produktüberstand >10 mm Randabsaugung und Begasung Siegelplatte Iteilig eloxiert und teflonisiert 4 cus. Temperaturfühler in den Ecken cur Temperaturüberwachung Siegelung bis zur Schneidung reichend	
	042	1	Sealing grid with filler plates : S W Z - U T 4 tracks 2 rows No. R530-33866/1 (neu) 13) for basic die 33866- 300 / Vario 1	X.25.32.13
	043	1	<pre>New design forming plate FDA 13) Forming plate - type 3 , F D A - L P 4 tracks</pre>	X.23.33.13
С			Execution: for aluminium max. ZT 100 mm with filler plates	
	044	1	New design plug mounting plate - non-heated plugs - 4 tracks 2 rows no. R530-33866 1 11) for subdivision 1 no. R530-33866/1	X.23.21.11
			for aluminum forming	
	045		Grid for FDA-UP - removable - 4 tracks 2 rows No. R530-33866/1 11) for subdivision 1 / No. R530-33866/1	X.23.27.11
			aus Stahl	
F	046		Special insert type 3 ' F D A - L P 4 tracks 2 rows No. R530-33852/2 FM 118,5 x 166 x 23,5 / PM 133,5 x 184 mm 13a) to suit basic die 33866- 300 / Vario 1	
С		en-hydPyssiddhaddannin	Ausführung: passend in Formplatte R530-33866/1 45 Grad Schräge pager Roller für Alu-Folien auch verwendbar als Begrenzungsplatte	_
С			für flexible Folie	_
F	081	1	TWF-Station compl anodized - New design TW-Station Top web forming station / no. 33866- 332	A.26.23.05 A.26.20.09 X.26.20.00
				X.26.20.01
			nuil	

Ä Pos	St Beschreibung	Preislisten-Nr.
	TW-single heating zur Verwendung mit flexibler Folie	A.26.20.01
	TW-forming without plug-assist compressed air forming + vacuum New design forming plate TWF 13)	A.26.22.00 A.26.21.02
F 080 F F F	1 Forming plate - type 3 / Top web forming station 4 tracks 2 rows / No. R530-33866/1 13) for subdivision 1 / No. R530-33866/1 FM 118,5 x 166 mm / PM 133,5 x 184 mm	X.26.25.13
F F F	Ausführung: Fixe Tiefe 12 mm für Alu- und flexible Folie mit 4 mm PVC-Rundschnur	
B 076	<pre>1 Guide roller for top web with 5 discs 11) for subdivision 1 / no. R530-33866/1</pre>	X.26.28.11
B 077 B B	<pre>l seal seam cooling unit - for cooling cutting zones - auf sep. Hubmechanik, mit Oberhub 60 mm</pre>	A.26.72.03
047	<pre>1 Hole punch for U-shaped slits - mounted after FWZ on lifting rails -</pre>	B.68.25.02
048 049 C 050	1 Support system BL 94 to suit die No 33866- 300 1 Discharge tray BL 94 to suit die No. 33866- 300 1 Die guard "DX" to suit die No. 33866- 300 guard pos. 1: FDA-infeed to suit die No. 33866- 300 /	B.68.63.01 B.68.63.03 B.27.10.90 A.27.21.01
C C	<pre>guard pos. 2: FDA-discharge 300 SF + LS</pre>	A.27.22.01 A.27.23.09
	Die guard pos. 4: SDA-discharge Guard position 5: R 530	B.27.24.01 B.27.25.01
051	4 Stainless steel loading grid with lift to suit subdivision 1 / no. R530-33866/1 über je 3 Takte reichend Innenmaβe ringsum 7,5 mm kleiner als FM Eintauchtiefe ca. 5 mm	X.12.04.13
052	4 lifting mechanism for loading grid stroke 50 mm for max. product protrusion 30 mm	X.12.04.05
	cycles per minute 15 cycles/min. product:	A.21.12.05 A.21.12.04
	Fertigmenüs momentan kalt abgefüllt z.B. Kartoffelgratin, Gemüse mit Soße,	

4 tracks - to suit R530-33866/1 / Vario 1

for use with Die No. 33867- 300

Ä Pos	St Beschreibung	Preislisten-Nr.
05 8 059	<pre>2 Sets of blades for edge trim ZT 160 3 Set of blades for 4 mm strip cut ZT 160 - PM 133,5 mm -</pre>	X.47.42.14 X.47.44.14
060	l Film edge trim rewind RSW.E3 with swing arm mit Randstreifenabriβkontrolle mit Näherungs- schalter Maschinenstop bei Streifenabriβ	B.48.02.01
061 G 082 G G	1 Trim removal unit for edge and middle strip trim 1 Punch cover for vacuum removal of punch waste for tear slits vacuum cleaner at the customer	A.48.04.00 B.48.11.01
062 C	Plexiglas drum D 150 / middle trim strip removal for product 30 mm to the top	B.48.05.00
063	1 plexiglas drum	A.48.05.01
E 064 E E E E	<pre>1 X/Y-linear co-ordinator unit incl. control unit for moving 2 inkjet heads cross the machine - mounted in Multiprint area to suit die No. 33866- 300 / incl.safety cover, magnetic switches for Excel 270, to be delivered by MU-INC.</pre>	A.53.02.02 052
065	<pre>1 Vibration unit with electrical vibrator - height adjustable - covering 2 cycles position: under 1st + 2nd cycle of loading grid</pre>	B.52.01.02
066	1 Discharge conveyor synchr. 800 mm w.neoprene belt - attached conveyor -	B.55.08.00 A.55.19.02
067	l Fork lift to ease die changes mit Aufnahmeplatte aus Kunststoff zum einfachen Wechseln der OF-Formstation	B.64.21.00
068	spare rod heaters for sealing plate die no. 33867- 300	X.95.10.14
069*	spare rod heaters for top web forming station die no. Nr. 33866-302	A.95.10.06
070*	<pre>1 add.sealing gaskets R530-33866/1 / Vario 1</pre>	X.95.16.10
071*	Extras 1: 1 cover plate for top web forming station, with MGS	A.95.18.01

Ä Pos	St Beschreibung	Preislisten-Nr.
C 078* C C C	Extras 2: 1 zus. Satz Platten R314 passend für Siegeleinschub 33867-300 ausgenommen für OF-Verformung 12 mm inkl. Distanzbuchsen und Schrauben für Vakuumpackungen	A.95.18.02
C 079* C	Extras 3 : 1 Hubmechanik für Kühleinrichtung mit Oberhub 60 mm	A.95.18.03
A -072 A	spare rod heaters for heating plate die no. 33865- 301	A.95.10.31
073 074 075	3 Operator manuals CE-Schild CE-Konformitätserklärung	A.28.91.08 M.95.90.08 M.95.90.08

Additional Equipment Provided by Domestic Vendors

- lea. VideoJet Excel Series 273se 2 Head Ink Jet Printer
 - * traversing system part of R530
 - Spare Parts Kit
 - Compressed Air Filter System
 - Alert Light
 - Console Stand
- l ea. Ames Engineering Web Lift Model AWL8C "Backsaver II"
- 1 ea. Busch Inc. Model RA0400 Vacuum Pump for seal die evacuation
- 1 ea. Busch Inc. Model WV1000 Roots Blower to assist RA0400
 Blower internally mounted in R530 at installation

1348 Sweening, Manite, A-B present Components


MULTIVAC


Sepp Haggenmuetter kG Verpacklungsmaschinen C-87787 Walterlschwenden

FORMATSKIZZE

mil max. Formatimessungen und Rackungsaussenmass with max. Inside and outside package dimensions avec dimensions interieures et exterieures max. de l'il embattage


P530





mit Randabsaugung und Begasung Aufreißschlitz in Sonderausführung Schweissnahtbreite 5.5 mm

 ✓ Bestellangabe Unterrolle ✓ Order data borrom film ✓ Donnees de commande film interes 	=80% FBU+3/+1	Diese Unterlage danf ohne unsere Zustwimung weder verweitgetligt noch Orinen zuggenglich ge-
'★★Bestellangabe Obertolie .★★Order data top tilm .★★Donnees de commande tilm sup	FB0'= FB0+1/-1	macht werden. Zuwidernandlungen veröftlichten zu Schodenersalz und sind sirolbar. Alle Rechle vorbehalten.
<u> 1555 </u>	rce	Formorivi
Unterschrift des - unden		33867



P.O. 94011S

Appendix 6.10

Multivac Y2K Documentation



09 February 1999

Mr. Neal Litman Rutgers University 120 New England Ave Piscataway, NJ 08854

RE: Year 2000

Dear Neal:

In response to your request, and those of many other business partners, Multivac is in the process of preparing a statement regarding our situation with computer issues and the date changeover to the year 2000. We anticipate this statement to be ready by the end of February 1999.

The statement will address the electronic controls of the various products we supply as well as the computerized business systems of both our North American Sales & Service Organization and our European Manufacturing Operations.

The main electronic controls of Multivac rollstock and chamber vacuum packaging machines (both past and present models) do not involve date based functions and therefore are unaffected by the changeover to the year 2000. Certain peripheral systems which do process dates (data acquisition systems) will be explained in greater detail in the forthcoming statement.

As a general statement regarding our computerized business systems: Multivac either has already upgraded software to versions which are certified to accept the year 2000 date change, or will be doing so before the middle of 1999. Additional details will be provided in the forthcoming statement.

This information is being provided to your company under the protection of the Year 2000 Information and Readiness Disclosure Act.

We will be maintaining your request on record and will supply you with a copy of the above referenced statement as soon as it is available.

Sincerely.

Donald E. Smith

EVP Operations/Manufacturing

(Smith



March 5, 1999

Mr. Neal Litman Rutgers University 120 New England Avenue Piscataway, NJ 08854

Dear Mr. Litman:

Multivac, Inc. has prepared the following information regarding year 2000 issues to provide our customers and other business partners with an understanding of our level of readiness for the millennium date change.

1. Products

Attached you will find information sheets on both past and present models of MULTIVAC packaging machines and MR labeling equipment.

2. Computerized Business Systems

Attached you will find information sheets concerning the readiness of the internal systems of the MULTIVAC and MR manufacturing facilities in Germany, also with comments regarding their suppliers.

Multivac, Inc. in North America has taken the following steps regarding our own computerized business systems:

- Uplift completed to Y2K Certified Compliant Version of Our Business Software JBA.
- Upgrade completed to Novell Operating system 4.11, which is certified as Y2K compliant.
- Remaining business systems such as voice mail, telephones etc. to be upgraded to Y2K compliant versions by mid 1999.

3. Suppliers of peripheral products sold with Multivac products

Multivac, Inc. has contacted and received assurance of year 2000 readiness from primary and secondary suppliers of products commonly sold in conjunction with the products manufactured by MULTIVAC and MR. This would include: vacuum pumps and blowers, printing devices, water chillers etc.

4. Suppliers of other products and services

Multivac, Inc. is in the process of securing Y2K assurances from suppliers of all products and services critical to the uninterrupted continuation of our business.

This information is being provided to your company under the protection of the Year 2000 Information and Readiness Disclosure Act.

Sincerely,

Donald E. Smith

Forald & Smith

Executive Vice President Manufacturing & Operations

DES:LB


4 Attachments

Multivac Packaging machines control units Explanation of "Year 2000 compatability"

Page 1 of 30.06.1998 pp/uni/grm



MC 90







This information is important for:

Sales


Service

Spare parts acquisition

Rollstock machine control units



MC



ST 62

Chamber machine control units

Computers may return false results from comparative functions after the annual change from 1999 to the year 2000, since often only the last two digits of the year number are used by the software and chips. This may lead to computer operations in which 00 is used instead of 2000 returning false results.

In this connection, Multivac has checked the "year 2000 compatability" of the control units installed in packaging machines.

1. Rollstock machine control units

Normally, no date or time functions are used by the control units. These control units are thus not affected by the "year 2000 problem".

Exception: in single cases, machines are equipped with the function Operating data logging (ODL). This option has the order numbers B 17.40.01 (R 530), S 17.40.01 (T 500) in the Multivac price list and contains a clock module with date and time.

Date and time functions before during and after the year change will be correctly processed within the control unit, but the year number will only be present as two digits. Conversion to a four digit value is available.

2. Chamber machine control units

Chamber machine control units have no integral date or time functions. The control units of these machines are therefore not affected.

All control units past and presently supplied on Multivac packaging machines have been confirmed to be able to accept the year change 1999-2000 without problem. As future control developments occur, all date and time related aspects will be checked to assure that this statement remains true.

ppa. Natterer

July 2000



MR Etikettiertechnik GmbH

Turn of the year 1999-2000

MR controls

Only controls with an integrated real time clock are facing the problem "turn of the year 1999-2000". Controls without an integrated date and time function are not concerned.

MK###-##-##	no	
MB###-##-##	no	
ML###-##-##	no	
MC###-##-##	no	
MD###-##-##	no	
MR2000	no	
MW###-##-##	no	date fields dependent on customer's laptop
TC001-01-02	yes	year 2000 from SN00000427
TC001-07-01	yes	year 2000 from SN00000733
TC001-08-02	yes	year 2000 from SN00000909
TC001-11-01	yes	year 2000 from SN00001067
TC001-13-01	yes	year 2000 from SN00001077

TC controls with a serial number (SN) lower than the ones mentioned above may be updated to achieve compatability regarding the date function for the year 2000.

MR software

Only software which processes variables/fields that are generated by a PC's real time clock is facing the problem "turn of the year 1999/2000". Date fields which are created by the customer within the layout have to consist of 4 figures. Fields consisting of only 2 figures indicate the turn switching from "99" to "00".

Independent of this fact, the BIOS of the customer's PC where the software is installed must be able to process the turn of the year 1999-2000.

MR PL23	yes	from version 2.9e, date fields dependent on the customer's PC
MR SL23	yes	from version 2.9e, date fields dependent on the customer's PC
MR TopLabel	yes	date fields dependent on the customer's PC
LAB600	yes	from version 1.6, date fields dependent on the customer's PC
MUDOT	no	Couplings with the PC's real time clock impossible



Wolfertschwenden, Juli 1998

Stellungnahme

Jahr 2000 Konformitāt

Hinsichtlich der Jahr-2000-Problematik in elektronischen Systemen und Steuerungen haben wir unsere Produkte, eigene Produktionsanlagen/-infrastruktur, Hardware/Software/Hilfsmittel in unseren DV-/Kommunikationssystemen und von uns eingesetzte Vorprodukte systematisch untersucht.

Erkannte Risiken und Probleme in Systemen werden bis zu Beginn 1999 korrigiert sein, bzw. die Systeme ausgetauscht sein.

Wir sind uns der mit dem Jahr 2000 verbundenen Risiken bewußt und haben diesen Risiken mit unseren Untersuchungen und eingeleiteten Maßnahmen vorgebeugt.

Eine Beeinträchtigung unserer Kunden und Geschäftspartner durch MULTIVAC hinsichtlich des Jahrtausendwechsels ist für uns nicht absehbar.

Statement

Year 2000 Compliance

As far as the Year 2000 issue in electronic systems and controls is concerned, we have systematically examined our products, own production lines and infrastructure, hardware/software/auxiliary devices in our data processing/communication systems as well as the products which we purchase from sub-suppliers.

By the beginning of the year 1999, any risks and problems which we may have found in the systems will have been corrected and/or the systems will have been replaced.

We are aware of the risks relating to the Year 2000 and have taken precautions by carrying out these investigations and by implementing corresponding measures.

We do not expect the turn of the century to present any problems to MULTIVAC customers and business partners.

MULTIVAC

Sepp Haggenmüller GmbH & Co.

ppa. Por Carl

Multivac Sepp Haggenmüller GmbH & Co. Behnhofstraße 4 D-B7787 Wolfertschwenden

Kommanditgesellschaft - Sitz: 87787 Wolfertschwenden - Amtsgericht Memmingen - HRA 8040 Persönlich haftende Gesellschaftern: Multivac Sepp Haggenmüller Verwaltungsgesellschaft mbH Sitz: 87787 Wolfertschwenden - Amtsgenicht Memmingen - HRB 10253 Geschäftstwer: Henz Brenne

Telefon +49 (0) 8334 601 214



MR Etikettiertechnik GmbH & Co. KG · Postfach 340 · D-32123 Enger

Enger, Oktober 1998

Stellungnahme

Jahr 2000 Konformität interner Systeme

Hinsichtlich der Jahr-2000-Problematik in elektronischen Systemem haben wir unsere eigene Hardware, Software und sonstige Hilfsmittel in unseren DV- und Kommunikationssystemen systematisch überprüft.

Die erkannten Risiken und Probleme in den Systemen werden bis zur Jahresmitte 1999 korrigiert oder die betroffenen Systeme ausgetauscht sein.

Wir sind uns der mit dem Jahr 2000 verbundenen Risiken bewußt und haben diesen Risiken mit unseren Überprüfungen und den eingeleiteten Maßnahmen vorgebeugt.

Eine Beeinträchigung unserer Kunden und Geschäftspartner durch MR Etikettiertechnik hinsichtlich des Jahrtausendwechsels ist für uns nicht absehbar.

Statement

Year 2000 Compliance of internal systems

As far as the Year 2000 issue in electronic systems is concerned, we have systematically examined our own hardware, software and other auxiliary devices in our data processing and communication systems.

By the middle of the year 1999, the risk and problems which we may have found in the systems will have been corrected and/or the corresponding systems will have been replaced.

We are aware of the risks relating to the Year 2000 and have take precautions by carrying out these investigations and by implementing corresponding measures.

We do not expect the turn of the century to present any problems to MR Etikettiertechnik's customers and business partners.

MR Etikettiertechnik GmbH & Co. KG

"C//

Gerloff V

i.V.

Vollenkemper

October 4, 1998

Shipping List For Multivac #667

Machine Section Forming/Loading Area	3500 lbs.
Machine Section Sealing/Punching	4000 lbs.
Machine Section Top Web Forming Unit	1000 lbs.
Busch Vacuum Pump	1700 lbs.
Busch Roots Blower	500 lbs.
Chains and Bottom Web Film Unwind Unit	400 lbs.
Videojet and Trim Removal Canister	300 lbs.
Box of Retrofit Parts	400 lbs.
Box of Miscellaneous Parts	200 lbs.
Tooling Hoist	150 lbs.
Film Hoist	150 lbs.

All shipping weights are approximate.

Appendix 6.12

FMTF Process Area "A"

Organization Chart for Redeployment of Multivac Packaging Lines

